
UNCONTROLLED DOCUMENT



PART NUMBER	SSI-LXR1612ID	REV.	С	
DATE	E.C.N. NUMBER AND REVISION COMMENTS			
09.19.94	09.19.94 UPDATED SPECS.			
10.16.01	E.C.N. #10BRDR. & REDRAWN IN 3D.		В	
07.14.11	E.C.N. #10BRDR. & REDRAWN.		С	

ELECTRO-OPTICAL	CHARACTERISTICS Ta=	=25°C	If=20mA		
PARAMETER	MIN	TYP	MAX	UNITS	UNITS
PEAK WAVELENGTH		635		nm	
FORWARD VOLTAGE		2.0	2.5	Vf	
REVERSE VOLTAGE	5.0			Vr	lr=100μA
AXIAL INTENSITY		30		mcd	lf=20mA
VIEWING ANGLE		60		2x theta	
EMITTED COLOR:	RED				
EPOXY LENS FINISH	t: RED DIFFUSED				

A LIMITS OF SAFE OPERATION AT 25	·c	
PARAMETER	MAX	UNITS
PEAK FORWARD CURRENT*	150	mA
STEADY CURRENT	30	mA
POWER DISSIPATION	105	mW
DERATE FROM 25°C	-1.6	mW/°C
OPERATING TEMP.	-40 TO +85	•C
STORAGE TEMP.	-40 TO +85	.C
SOLDERING TEMP.	+260	<b>.</b> C

SEC. MAX.

\* t<10µS

2.0mm FROM BODY

## NOTES:

- 1. SSI-LXR1612, CHROME HOUSING.
- 2. SSL-LX3054ID, RED LED.
- A 3. SSH-LXH1612BSG, BUSHING. INSERT AND CRIMP.

\*UNLESS OTHERWISE SPECIFIED TOLERANCES PER DECIMAL PRECISION ARE: X=±1 (±0.039), X.X=±0.5 (±0.020), X.XX=±0.25 (±0.010), X.XXX=±0.127 (±0.005). LEAD SIZE=±0.05 (±0.002), LEAD LENGTH=±0.75 (±0.030). MIN=  $^{+DECIMAL}_{-0.00}$  PRECISION MAX.=  $^{+0.00}_{-DECIMAL}$  PRECISION UNCONTROLLED DOCUMENT



290 E. HELEN ROAD PALATINE, IL 60067-6976 PHONE: +1.847.359.2790 FAX: +1.847.359.6538

T-3mm (T-1) 635nm RED LED PANEL INDICATOR, RED DIFFUSED LENS.

\*\*THE SPECIFICATIONS MAY CHANGE AT ANY TIME WITHOUT NOTICE DUE TO NEW MATERIALS OR PRODUCT IMPROVEMENT.\*\*

CONFIDENTIAL INFORMATION
THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE PROPERTY OF LUMEX INC. EXCEPT AS SPECIFICALLY AUTHORIZED IN WRITING BY LUMEX INC., THE HOLDER OF THIS DOCUMENT SHALL KEEP ALL INFORMATION CONTAINED HEREIN CONFIDENTIAL AND SHALL PROTECT SAME IN WHOLE OR IN PART FROM DISCLOSURE AND DISSEMINATION TO ALL THIRD PARTIES.

DATE: 07.14.11 DRAWN BY: AΒ PAGE: 1 OF CHKD BY: KF SCALE: NTS APRVD BY: SS UNIT: mm [INCH] (Pb)