
UNCONTROLLED DOCUMENT

PART NUMBER	SSI-LXR3612SID-150	REV.	Α
DATE	E.C.N. NUMBER AND REVISION COMMENTS		REV.
7.14.11	E.C.N. #10BRDR. & REDRAWN.		Α



ELECTRO-OPTICAL CH	ARACTERISTICS Ta=	25°C	If=20mA		
PARAMETER	MIN	TYP	MAX	UNITS	UNITS
PEAK WAVELENGTH		636		nm	
FORWARD VOLTAGE		2.1	2.5	Vf	
REVERSE VOLTAGE	5.0			Vr	lr=100μA
AXIAL INTENSITY		100		mcd	If=10mA
VIEWING ANGLE		60		2x theta	
EMITTED COLOR:	RED				
EPOXY LENS FINISH:	RED DIFFUSED				

PIMIT	ΛF	CAFE	OPERATION	۸Т	25*0
LIMITS	Ur	SALE	UPERATION	ΑI	200

PARAMETER	MAX	UNITS
PEAK FORWARD CURRENT*	150	mA
STEADY CURRENT	30	mA
POWER DISSIPATION	105	mW
DERATE FROM 25°C	-1.6	mW/*C
OPERATING TEMP.	-40 TO +85	·C
STORAGE TEMP.	-40 TO +85	.C
* t<10µS		

NOTES:

- SSL-LX3054SYD, RED LED, TRIM LEADS TO 5mm.
 SSI-LXR3612 HOLDER, CHROME FINISH.
- 3. SSH-LXH1612BSG, BUSHING. INSERT AND CRIMP.
- 4. ANODE LEAD: LXP-WST26RDTOC, 26 AWG. STRANDED, RED INSULATION, CUT TO 460mm LONG, STRIP ENDS 2mm AND 9.5mm.
- 5. CATHODE LEAD: LXP-WST26BLTOC, 26 AWG. STRANDED, BLACK INSULATION,
- CUT TO 460mm LONG, STRIP ENDS 2mm AND 9.5mm.
- 6. SOLDER LED LEADS TO WIRE LEADS.

*UNLESS OTHERWISE SPECIFIED TOLERANCES PER DECIMAL PRE	CISION ARE: $X=\pm 1$ (± 0.039), $X.X=\pm 0.5$	(± 0.020) , $X.XX = \pm 0.25$ (± 0.010) , $X.XXX = \pm 0.127$ (± 0.005) .	LEAD SIZE= ± 0.05 (± 0.002), LEAD LENGTH= ± 0.75 (± 0.030). MIN= $^{+DECIMAL}_{-0.00}$ PRECISION MAX.= $^{+0.00}_{-DECIMAL}$ PRECISION	UNCONTROLL	ED DOCUI	MENT
				DATE 07 14 11	DDAWN DV	



290 E. HELEN ROAD PALATINE, IL 60067-6976 PHONE: +1.847.359.2790 FAX: +1.847.359.6538

T-3mm (T-1) 636nm RED PANEL INDICATOR, RED DIFFUSED LENS, 6" WIRE LEADS.

THE SPECIFICATIONS MAY CHANGE AT ANY TIME WITHOUT NOTICE DUE TO NEW MATERIALS OR PRODUCT IMPROVEMENT.

CONFIDENTIAL INFORMATION
THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE PROPERTY OF LUMEX INC. EXCEPT AS SPECIFICALLY AUTHORIZED IN WRITING BY LUMEX INC., THE HOLDER OF THIS DOCUMENT SHALL KEEP ALL INFORMATION CONTAINED HEREIN CONFIDENTIAL AND SHALL PROTECT SAME IN WHOLE OR IN PART FROM DISCLOSURE AND DISSEMINATION TO ALL THIRD PARTIES.

DATE: 07.14.11 DRAWN BY: AΒ PAGE: 1 OF CHKD BY: KF SCALE: NTS APRVD BY: KF UNIT: mm [INCH] (Pb)