



- 1 ALL PARTS PACKAGED UNASSEMBLED.
- 2 AS SHOWN ABOVE, THIS KIT CONSISTS OF 2 STRAIN RELIEF HALVES, 2 #4-40 SCREWS, 2 #4-40 NUTS & 2 #4-40 MOUNTING SCREWS.
- 3 SAME AS SHOWN, EXCEPT: EACH PART IS INDIVIDUALLY BULK PACKED FOR MULTIPLE KIT ORDERS.
- 4 OBSOLETE

MOD	LOC	DIST	P	F	ZONE	LTR	DESCRIPTION	DATE	APPD
22	BD	39					REDRAWN ON CAD	5-16-90	

REMARKS	SIZE IDENT LETTER	CABLE DIA	BULK PACKED KIT NO	INDIVIDUAL KIT NO
1	B	.225	747099-8	747099-7
	E	.300	747099-6	747099-5
	H	.375	747099-4	747099-3
	K	.430	747099-2	747099-1

DO NOT SCALE PRINT. UNLESS SPECIFIED DIMENSIONS IN INCHES TOLERANCES ON: 2 PLC DEC ± .005 3 PLC DEC ± .005 ANGLES MATERIAL

DR 5-16-90 J GALLUCI BG
 CHK - 6-15-90
 APPD - 7-9-90
 APPD - 7-16-90
 PRODUCT SPEC

NAME: AMP INCORPORATED, Harrisburg, Pa. 17105

CABLE CLAMP KIT, SIZE 2, 15 POSN, 180°, PLATED PLASTIC, AMPLIMITE™

FINISH: SEE CALLOUT

APPLICATION SPEC

SCALE: 2:1

FSCH NO: 00779

DRAWING NO: 747099

SHEET: 1 OF 1